RECOMMENDED CONDITIONS OF APPROVAL AND STANDARD DEVELOPMENT REQUIREMENTS JANUARY 28, 2019

Planning Application 2018-7432

275 N. Mathilda (APNs:165-27-007,008,009)

Construct a new 123,000 square foot, four-story office building, 4.5-level parking structure and associated site work and landscaping. The project will result in 80% FAR.

The following Conditions of Approval [COA] and Standard Development Requirements [SDR] apply to the project referenced above. The COAs are specific conditions applicable to the proposed project. The SDRs are items which are codified or adopted by resolution and have been included for ease of reference, they may not be appealed or changed. The COAs and SDRs are grouped under specific headings that relate to the timing of required compliance. Additional language within a condition may further define the timing of required compliance. Applicable mitigation measures are noted with "Mitigation Measure" and placed in the applicable phase of the project.

In addition to complying with all applicable City, County, State and Federal Statutes, Codes, Ordinances, Resolutions and Regulations, Permittee expressly accepts and agrees to comply with the following Conditions of Approval and Standard Development Requirements of this Permit:

GC: THE FOLLOWING GENERAL CONDITIONS AND STANDARD DEVELOPMENT REQUIREMENTS SHALL APPLY TO THE APPROVED PROJECT.

GC-1. CONFORMANCE WITH APPROVED PLANNING APPLICATION:

All building permit drawings and subsequent construction and operation shall substantially conform with the approved planning application, including: drawings/plans, materials samples, building colors, and other items submitted as part of the approved application. Any proposed amendments to the approved plans or Conditions of Approval are subject to review and approval by the City. The Director of Community Development shall determine whether revisions are considered major or minor. Minor changes are subject to review and approval by the Director of Community Development. Major changes are subject to review at a public hearing. [COA] [PLANNING]

The approved entitlements shall be null and void two years from the date of approval by the final review authority if the approval is not exercised, unless a written request for an extension is received prior to the expiration date and is approved by the Director of Community Development. [SDR] (PLANNING)

GC-3. ENTITLEMENTS—DISCONTINUANCE AND EXPIRATION:

The entitlements shall expire if discontinued for a period of one year or more. [SDR] (PLANNING)

GC-4. INDEMNITY:

The applicant/developer shall defend, indemnify, and hold harmless the City, or any of its boards, commissions, agents, officers, and employees (collectively, "City") from any claim, action, or proceeding against the City to attack, set aside, void, or annul, the approval of the project when such claim, action, or proceeding is brought within the time period provided for in applicable state and/or local statutes. The City shall promptly notify the developer of any such claim, action or proceeding. The City shall have the option of coordinating the defense. Nothing contained in this condition shall prohibit the City from participating in a defense of any claim, action, or proceeding if the City bears its own attorney's fees and costs, and the City defends the action in good faith. [COA] [OFFICE OF THE CITY ATTORNEY]

GC-5. NOTICE OF FEES PROTEST:

As required by California Government Code Section 66020, the project applicant is hereby notified that the 90-day period has begun as of the date of the approval of this application, in which the applicant may protest any fees, dedications, reservations, or other exactions imposed by the city as part of the approval or as a condition of approval of this development. The fees, dedications, reservations, or other exactions are described in the approved plans, conditions of approval, and/or adopted city impact fee schedule. [SDR] [PLANNING / OCA]

GC-6. STORMWATER MANAGEMENT PLAN:

Project is subject to Provision C3, of the Municipal Regional Stormwater Permit Order No. R2-2009-0074, as determined by a completed "Stormwater Management Plan Data Form", and therefore must submit a Stormwater Management Plan as per SMC 12.60.140 prior to issuance of the building permit. [SDR] [PLANNING]

GC-7. AVIGATION EASEMENT

Per the Airport Land Use Commission, the project shall provide an Avigation Easement to be dedicated to the United States Government to be consistent with Moffett Federal Airfield Comprehensive Land Use Plan (CLUP) to be recorded with Santa Clara County. [COA] [PLANNING, ALUC]

GC-8. COMMUNITY BENEFITS PROGRAM

Project shall complete all the benefits noted in the approved Community Benefits Program prior to the Occupancy Permit. The flexible community benefits shall be a monetary contribution of \$848,700. [COA] [PLANNING]

GC-9. TRANSPORTATION MANAGEMENT ASSOCIATION:

The property owner and future tenants are required to join the Peery Park Transportation Management Association and maintain membership within the organization. [COA] [PLANNING]

GC-10. ENVIRONMENTAL MITIGATION MEASURES:

The project shall pay its fair share contribution towards all mitigation measures identified in the Peery Park Specific Plan Environmental Impact Report (EIR) Mitigation Measures. [COA] [PUBLIC WORKS/PLANNING] **MITIGATION MEASURE**

GC-11. PUBLIC IMPROVEMENTS:

Developer shall install public improvements as required by the City, including but not limited to, curb & gutter, sidewalks, driveway approaches, street pavements, utility extensions and connections, meters/vaults, trees and landscaping, traffic signs, striping, street lights, etc.

All public improvements shall be designed and constructed in accordance with current City design guidelines, standard details and specifications, and Americans with Disabilities Act (ADA) requirements where applicable, unless otherwise approved by the Department of Public Works. Sheets TM 1 thru TM-5 and off-site improvements Sheets C1.0 thru C8.0 dated 01/14/19 are subject to change during the plan check process.

The developer is required to complete the installation of the on-site public water main prior to the issuance of the Building Permit.

The developer is required to complete the installation of all public improvements and other improvements deemed necessary by the Public Works Department, prior to occupancy of the first building, or to the satisfaction of the Public Works Department. [COA] [PUBLIC WORKS]

GC-12. OFF-SITE IMPROVEMENT PLANS:

Submit off-site improvement plans separate from the Building on-site improvement plans as the off-site improvement plans are approved

through a Public Works Encroachment Permit process. Sheets TM 1 thru TM-5 and off-site improvements Sheets C1.0 thru C8.0 dated 01/14/19 are subject to change during the plan check process.

GC-13. WATER MAIN RELOCATION PLANS:

Submit improvement plans for the on-site public water main relocation separate from the off-site improvement plans and the Building on-site improvement plans as the water line relocation plans are approved through a Public Works Encroachment Permit process. The water line relocation shown Sheets TM 1 thru TM-5 and off-site improvements Sheets C1.0 thru C8.0 dated 01/14/19 are subject to change during the plan check process.

[SDR] [PUBLIC WORKS]

GC-14. ENCROACHMENT PERMIT:

Prior to any work in the public right-of-way, obtain an encroachment permit with insurance requirements for all public improvements including a traffic control plan per the latest California Manual on Uniform Traffic Control Devices (MUTCD) standards to be reviewed and approved by the Department of Public Works. [COA] [PUBLIC WORKS]

GC-15. RECORDATION OF-PARCEL MAPS:

This project is subject to, and contingent upon recordation of parcel map for lot mergers. The submittal, approval and recordation of the parcel map(s) shall be in accordance with the provisions of the California Subdivision Map Act and Sunnyvale Municipal Code Title 18 Subdivision requirements. Parcel map(s) shall be recorded prior to any grading or building permit issuance of any building located on that certain lot as shown on the corresponding parcel map. [COA] [PUBLIC WORKS]

MM: THE FOLLOWING CONDITIONS SHALL BE ADDRESSED AND MITIGATION MEASURES NOTED FOR PPSP PROGRAM EIR – MMRP AS RELEVANT TO THIS PROJECT

MM-1. PEERY PARK SPECIFIC PLAN – MITIGATION, MONITORING & REPORTING PROGRAM (MMRP):

The project applicant shall demonstrate compliance with the Mitigation and Monitoring Reporting Program (MMRP) as required in the Peery Park Specific Plan Environmental Impact Report (EIR) and Transportation Impact Analysis (TIA) Mitigation Measures. [COA] [PLANNING/PUBLIC WORKS]

PS: THE FOLLOWING CONDITIONS SHALL BE MET PRIOR TO SUBMITTAL OF BUILDING PERMIT, AND/OR GRADING PERMIT.

PS-1. EXTERIOR MATERIALS REVIEW:

Final exterior building materials and color scheme are subject to review and approval by the Director of Community Development prior to submittal of a building permit. [COA] [PLANNING]

PS-2. SANITARY SEWER ANALYSIS:

Prior to first off-site plan check submittal, submit a focused sanitary sewer analysis, to be reviewed and approved by the City, identifying the overall project impact to the City's existing sanitary sewer main(s). This includes, but is not limited to, the following:

- a) A detailed estimate of water consumption in gallons per day or estimate of sanitary sewer discharge in gallons per day; and
- b) Any incremental impact that will result from the new project in comparison to the existing sewer capacity of the immediate downstream mainline as needed, and allocation of wastewater discharge from the project site to each of the proposed laterals. Any deficiencies in the existing system in the immediate vicinity of the project will need to be addressed and resolved at the expense of the developer as part of the off-site improvement plans. Any mitigation improvements needed shall be incorporated into the first plan check submittal.

Per the Peery Park Specific Plan, the developer shall either be assessed wastewater system impact fees or be required to construct specific wastewater main improvements as determined from the sanitary sewer analysis and shall be incorporated into the first off-site improvement plan check submittal. If required to construct sewer improvements, a fee credit may be applied up to the cost of improvements. If construction costs exceed the fee credit, a Reimbursement Agreement may be entered with the Developer by the City. [COA] [PUBLIC WORKS]

BP: THE FOLLOWING CONDITIONS SHALL BE ADDRESSED ON THE CONSTRUCTION PLANS SUBMITTED FOR ANY DEMOLITION PERMIT, BUILDING PERMIT, GRADING PERMIT, AND/OR ENCROACHMENT PERMIT AND SHALL BE MET PRIOR TO THE ISSUANCE OF SAID PERMIT(S).

Final plans shall include all Conditions of Approval included as part of the approved application starting on sheet 2 of the plans. [COA] [PLANNING]

BP-2. RESPONSE TO CONDITIONS OF APPROVAL:

A written response indicating how each condition has or will be addressed shall accompany the building permit set of plans. [COA] [PLANNING]

BP-3. NOTICE OF CONDITIONS OF APPROVAL:

A Notice of Conditions of Approval shall be filed in the official records of the County of Santa Clara and provide proof of such recordation to the City prior to issuance of any City permit, allowed use of the property, or Final Map, as applicable. The Notice of Conditions of Approval shall be prepared by the Planning Division and shall include a description of the subject property, the Planning Application number, attached conditions of approval and any accompanying subdivision or parcel map, including book and page and recorded document number, if any, and be signed and notarized by each property owner of record.

For purposes of determining the record owner of the property, the applicant shall provide the City with evidence in the form of a report from a title insurance company indicating that the record owner(s) are the person(s) who have signed the Notice of Conditions of Approval. [COA] [PLANNING]

BP-4. BLUEPRINT FOR A CLEAN BAY:

The building permit plans shall include a "Blueprint for a Clean Bay" on one full sized sheet of the plans. [SDR] [PLANNING]

BP-5. RECYCLING AND SOLID WASTE ENCLOSURE:

The building permit plans shall include details for the installation of a recycling and solid waste enclosure. The required solid waste and recycling enclosure shall:

- a) Match the design, materials and color of the main building.
- b) Be of masonry construction. [COA] [PLANNING]

BP-6. RECYCLING AND SOLID WASTE CONTAINER:

All recycling and solid waste containers shall be metal or State Fire Marshall listed non-metallic. The building permit plans shall provide details illustrating compliance with this condition. [COA] [PLANNING]

BP-7. SOLID WASTE DISPOSAL PLAN:

A detailed recycling and solid waste disposal plan shall be submitted for review and approval by the Director of Community Development prior to issuance of building permit. [COA] [PLANNING]

BP-8. ROOF EQUIPMENT:

Roof vents, pipes and flues shall be combined and/or collected together on slopes of roof or behind parapets out of public view as per Title 19 of the Sunnyvale Municipal Code and shall be painted to match the roof. [COA] [PLANNING]

BP-9. FEES AND BONDS:

The following fees and bonds shall be paid in full prior to issuance of building permit.

- a) TRANSPORTATION IMPACT FEE Pay Traffic Impact fee for the net new trips resulting from the proposed project, estimated at \$333,732, prior to issuance of a Building Permit. (SMC 3.50). [SDR] [PLANNING]
- b) HOUSING MITIGATION FEE Pay Housing Mitigation fee estimated at \$980,512.50 prior to issuance of a Building Permit. (SMC 19.22). [SDR] [PLANNING]
- c) ART IN PRIVATE DEVELOPMENT BOND A bond, letter of credit, cash deposit or other similar security instrument for 1% of the construction valuation of the entire office development project will be required prior to issuance of a building permit. The bond will not released until completion and installation of the artwork requirement including related landscaping, lighting, base work and commemorative plaque. [PLANNING] [SDR]
- d) PERRY PARK SPECIFIC PLAN- Prior to issuance of a building, calculate and pay the following fees estimated below (current values shown adjusted yearly to reflect cost of living changes):
 - (i) Peery Park Specific Plan Fee at 0.082% of the total construction value of the project;
 - (ii) Peery Park Specific Plan Infrastructure Fee Wastewater at a rate of \$3.12 per net new square feet, estimated for the project at \$224,406.
 - (iii) Peery Park Specific Plan Infrastructure Fee Water at a rate of \$3.12 per net new square feet. estimated for the project at \$224,406.
 - (iv) Peery Park Specific Plan Sense of Place Fee at a rate of \$2.41 per net new square feet estimated for the project at \$173,339
 - (v) Peery Park Specific Plan traffic mitigation measure fees to be calculated based on fair share contribution as noted in MMT-2a, 2b and 3 in the PPSP Mitigation and Monitoring Program.

BP-10. LANDSCAPE PLAN:

Landscape and irrigation plans shall be prepared by a certified professional, and shall comply with Sunnyvale Municipal Code Chapter 19.37 requirements. Landscape and irrigation plans are subject to review and approval by the Director of Community Development through the submittal of a Miscellaneous Plan Permit (MPP). The landscape plan shall include the following elements:

- b) All areas not required for parking, driveways or structures shall be landscaped.
- c) Provide trees at minimum 30 feet intervals alongside and rear property lines, except where mature trees are located immediately adjoining on neighboring property.
- e) Ten percent (10%) shall be 24-inch box size or larger and no tree shall be less than 15-gallon size.
- f) Any "protected trees", (as defined in SMC 19.94) approved for removal, shall be replaced with a specimen tree of at least 36-inch box size.
- g) Ground cover shall be planted to ensure full coverage eighteen months after installation. [COA] [PLANNING]

BP-11. LANDSCAPE MAINTENANCE PLAN:

Prepare a landscape maintenance plan subject to review and approval by the Director of Community Development prior to issuance of building permit. [COA] [PLANNING]

BP-12. TREE PROTECTION PLAN:

Prior to issuance of a Demolition Permit, a Grading Permit or a Building Permit, whichever occurs first, obtain approval of a tree protection plan from the Director of Community Development. Two copies are required to be submitted for review. The tree protection plan shall include measures noted in Title 19 of the Sunnyvale Municipal Code and at a minimum:

- a) An inventory shall be taken of all existing trees on the plan including the valuation of all 'protected trees' by a certified arborist, using the latest version of the "Guide for Plant Appraisal" published by the International Society of Arboriculture (ISA).
- b) All existing (non-orchard) trees on the plans, showing size and varieties, and clearly specify which are to be retained.
- c) Provide fencing around the drip line of the trees that are to be saved and ensure that no construction debris or equipment is stored within the fenced area during demolition and construction.

d) The tree protection plan shall be installed prior to issuance of any Building or Grading Permits, subject to the on-site inspection and approval by the City Arborist and shall be maintained in place during the duration of construction and shall be added to any subsequent building permit plans. [COA] [PLANNING/CITY ARBORIST]

BP-13. STORMWATER MANAGEMENT PLAN:

Submit two copies of a Stormwater Management Plan subject to review and approval by Director of Community Development and third party certification, pursuant to SMC 12.60, prior to issuance of building permit. [COA] [PLANNING/PUBLIC WORKS]

BP-14. STORM WATER MANAGEMENT PLAN THIRD PARTY CERTIFICATION: Third party certification of the Storm Water Management Plan is required per the following guidance: City of Sunnyvale – Storm Water Quality BMP Applicant Guidance Manual for New and Redevelopment Projects - Addendum: Section 3.1.2 Certification of Design Criteria Third-Party Certification of Storm Water Management Plan Requirements. The third-party certification shall be provided prior to building permit issuance. [SDR] [PLANNING/PUBLIC WORKS]

BP-15. BEST MANAGEMENT PRACTICES - STORMWATER:

The project shall comply with the following source control measures as outlined in the BMP Guidance Manual and SMC 12.60.220. Best management practices shall be identified on the building permit set of plans and shall be subject to review and approval by the Director of Public Works:

- a) Storm drain stenciling. The stencil is available from the City's Environmental Division Public Outreach Program, which may be reached by calling (408) 730-7738.
- b) Landscaping that minimizes irrigation and runoff, promotes surface infiltration where possible, minimizes the use of pesticides and fertilizers, and incorporates appropriate sustainable landscaping practices and programs such as Bay-Friendly Landscaping.
- c) Appropriate covers, drains, and storage precautions for outdoor material storage areas, loading docks, repair/maintenance bays, and fueling areas.
- d) Covered trash, food waste, and compactor enclosures.
- e) Plumbing of the following discharges to the sanitary sewer, subject to the local sanitary sewer agency's authority and standards:
 - i) Discharges from indoor floor mat/equipment/hood filter wash racks or covered outdoor wash racks for restaurants.

- ii) Dumpster drips from covered trash and food compactor enclosures.
- iii) Discharges from outdoor covered wash areas for vehicles, equipment, and accessories.
- iv) Swimming pool water, spa/hot tub, water feature and fountain discharges if discharge to onsite vegetated areas is not a feasible option.
- v) Fire sprinkler test water, if discharge to onsite vegetated areas is not a feasible option. [SDR] [PLANNING]

BP-16. CITY STREET TREES:

The landscape plan shall include street trees and shall be submitted for review and approval by the City Arborist prior to issuance of building permit. [COA] [ENGINEERING/CITY ARBORIST]

BP-17. EXTERIOR LIGHTING PLAN:

Prior to issuance of a Building Permit submit an exterior lighting plan, including fixture and pole designs, for review and approval by the Director of Community Development. Driveway and parking area lights shall include the following:

- a) Sodium vapor (or illumination with an equivalent energy savings).
- b) Pole heights to be uniform and compatible with the areas, including the adjacent residential areas. Light standards shall not exceed 18 feet on the interior of the project and 8 feet in height on the periphery of the project near residential uses.
- c) Provide photocells for on/off control of all security and area lights.
- d) All exterior security lights shall be equipped with vandal resistant covers.
- e) Wall packs shall not extend above the roof of the building.
- f) Lights shall have shields to prevent glare onto adjacent residential properties. [COA] [PLANNING]

BP-18. PHOTOMETRIC PLAN:

Prior to issuance of a Building Permit submit a contour photometric plan for approval by the Director of Community Development. The plan shall meet the specifications noted in the Standard Development Requirements. [COA] [PLANNING]

BP-19. LIGHTING POLE HEIGHTS:

Pole heights shall not to exceed 18 feet. [COA] [PLANNING]

BP-20. PARKING MANAGEMENT PLAN (NONRESIDENTIAL):

A Parking Management Plan shall be submitted for review and approval by the Director of Community Development prior to issuance of a building permit. The Parking Management Plan shall include the following:

- a) Employee parking locations shall be away from the building, in parking spaces that are the least used.
- b) Specify the location and term of short-term parking.
- c) Allow the use of valet parking when appropriate on sites with limited parking.
- d) Employees shall be required to park on the site.
- e) Provide adequate signage to direct traffic and pedestrians [COA] [PLANNING]

BP-21. BICYCLE SPACES:

Provide 25 Class I and 25 Class II bicycle parking spaces per Citywide Design Guidelines and as approved by the Director of Community Development. Clearly indicate the location and the number of bicycle parking spaces on the Building Permit plans. [COA] [PLANNING]

BP-22. CARPOOL PARKING:

A total of 29 preferential parking spaces shall be reserved and so marked in the closest possible rows adjoining the building (allowing for visitor, disabled and pool van parking) for exclusive use by carpool vehicles carrying at least two employees per vehicle. [COA] [PLANNING]

BP-23. GREEN BUILDING:

The project shall meet the following green building requirements:

- a) Final plans shall incorporate a completed LEED green building checklist demonstrating the new building achieves a minimum LEED Gold level for Core and Shell, with efforts to achieve Platinum level as verified by a qualified LEED consultant and shall be submitted to USGBC for formal certification.
- b) Subsequent building permit plans for interior tenant improvements for the new buildings shall incorporate a completed LEED green building checklist demonstrating the project design achieves a minimum LEED Gold level for Commercial Interiors, with efforts to achieve Platinum level, as verified by a qualified LEED consultant and shall be submitted for USGBC for formal certification [COA] [PLANNING]

BP-24. CONSTRUCTION MANAGEMENT PLAN:

The project applicant shall implement a Construction Management Plan (CMP) to minimize impacts of construction on surrounding residential uses to the extent possible. The CMP shall be subject to review and approval by the Director of Community Development prior to issuance of a demolition permit, grading permit, or building permit. The CMP shall identify measures to minimize the impacts of construction including the following:

- a) Measures to control noise by limiting construction hours to those allowed by the SMC, avoiding sensitive early morning and evening hours, notifying residents prior to major construction activities, and appropriately scheduling use of noise-generating equipment.
- b) Use 'quiet' models of air compressors and other stationary noise sources where such technology exists.
- c) Equip all internal combustion engine-driven equipment with mufflers, which are in good condition and appropriate for the equipment.
- d) Locate all stationary noise-generating equipment, such as air compressors and portable power generators, as far away as possible from residences or other noise-sensitive land uses.
- e) Locate staging areas and construction material areas as far away as possible from residences or noise-sensitive land uses.
- f) Route all construction traffic to and from the project site via designated truck routes where possible. Prohibit constructionrelated heavy truck traffic in residential areas where feasible. Obtain approval of proposed construction vehicle truck routes from the Department of Public Works.
- g) Manage construction parking so that neighbors are not impacted by construction vehicles. When the site permits, all construction parking shall be on-site and not on the public streets.
- h) Prohibit unnecessary idling of internal combustion engine-driven equipment and vehicles.
- i) Notify all adjacent business, residents, and noise-sensitive land uses of the construction schedule in writing. Notify nearby residences of significant upcoming construction activities at appropriate stages in the project using mailing or door hangers.
- j) Designate a "disturbance coordinator" who would be responsible for responding to any local complaints about construction noise. The disturbance coordinator will determine the cause of the noise complaint and will require that reasonable measures warranted to correct the problem be implemented. Conspicuously post a telephone number for the disturbance coordinator at the construction site and include it in the notice sent to neighbors regarding the construction schedule. [COA] [PLANNING]

BP-25. BIOLOGICAL RESOURCES—BIRD NESTING:

Construction activities shall avoid the nesting season to the extent feasible.

- a) If construction would commence anytime during nesting/breeding season of native bird species (typically February through August in the region), a qualified biologist shall conduct a preconstruction survey of the project vicinity for nesting/breeding birds at least 30 days prior to the start of construction activities. The survey shall determine if active raptor nests or other species protected by the Migratory Bird Treaty Act are present within the construction zone or within 250 ft. of construction for raptors and 50 ft. of the construction zone for other migratory birds. The survey area shall include all trees and shrubs within that zone that have the potential to support nesting birds.
- b) If active nests are found in areas that could be directly affected or are within 250 ft. of construction for raptors and 50 ft. for other migratory birds, a no-disturbance buffer zone shall be created around active nests during the breeding season or until a qualified biologist determines that all young have fledged. Once the young have fledged, tree removal and other construction activities may commence.
- c) Any construction buffer zone must be implemented and maintained during construction activities.
- BP-26. DEMOLITION/CONSTRUCTION/RECYCLING WASTE REPORT FORM: To mitigate the impacts of large projects on local waste disposal and recycling levels, demolition waste weights/volumes, construction weights/volumes, and recycling weights/volumes are to be reported to the City using Sunnyvale.wastetracking.com hosted by Green Halo. As part of the project's construction specifications, the developer shall track the type, quantity, and disposition of materials generated, and submit these records through the website both periodically and at project completion. [COA] [ENVIRONMENTAL SERVICES]

BP-27. SOLID WASTE AND RECYCLING ENCLOSURE:

The building permit plans shall include details for the installation of recycling and solid waste enclosures that are consistent with SMC 19.38.030. The solid waste disposal and recycling facilities within the enclosure area or within buildings shall be designed with adequate size, space and clearance based upon City's latest guidelines. The required enclosures shall:

- a) Match the design, materials and color of the main building;
- b) Be of masonry construction;
- c) Be screened from view;
- d) All gates, lids and doors shall be closed at all times;
- e) Shall not conflict with delivery/receiving areas;

- f) Shall be consistent with the approved Solid Waste and Recycling Management Plan;
- g) Solid waste and recycling diversion systems shall be incorporated into the facilities and tenant improvements. [COA] [PLANNING/ENVIRONMENTAL SERVICES]

BP-28. SOLID WASTE DISPOSAL AND RECYCLING DESIGN PLAN:

A detailed solid waste disposal and recycling design plan shall be submitted for review and approval by the Director of Community Development prior to issuance of building permit. The solid waste disposal plan and building permit plans shall demonstrate compliance with current City requirements and guidelines for non-residential projects. [COA] [PLANNING/ENVIRONMENTAL SERVICES]

BP-29. ENVIRONMENTAL MITIGATION MEASURES:

The project applicant shall demonstrate compliance with the Mitigation and Monitoring Reporting Program (MMRP) as required in the Peery Park Specific Plan Environmental Impact Report (EIR) Mitigation Measures. [COA] [PUBLIC WORKS]

BP-30. STORMWATER MANAGEMENT PLAN:

Submit two copies of a Stormwater Management Plan subject to review and approval by Director of Community Development, pursuant to SMC 12.60, prior to issuance of building permit. The Stormwater Management Plan shall include an updated Stormwater Management Data Form. [COA] [PLANNING/ENVIRONMENTAL SERVICES] 7.

BP-31. STORMWATER MANAGEMENT PLAN THIRD-PARTY CERTIFICATION: Third-party certification of the Stormwater Management Plan is required per the following guidance: City of Sunnyvale – Stormwater Quality BMP Applicant Guidance Manual for New and Redevelopment Projects - Addendum: Section 3.1.2 Certification of Design Criteria Third-Party Certification of Stormwater Management Plan Requirements. The third-party certification shall be provided prior to building permit issuance. [SDR] [PLANNING/ENVIRONMENTAL SERVICES]

BP-32. CONSTRUCTION MATERIAL AND STAGING:

All construction related materials, equipment, and construction workers parking need to be managed on-site and not located in the public right-of-ways or public easements. [COA] [PUBLIC WORKS]

BP-33. PARCEL MAP:

This project is subject to, and contingent upon recordation of parcel map for lot mergers. The submittal, approval and recordation of the parcel map(s) shall be in accordance with the provisions of the

California Subdivision Map Act and Sunnyvale Municipal Code Title 18 Subdivision requirements. Parcel map(s) shall be recorded prior to any grading or building permit issuance of any building located on that certain lot as shown on the corresponding parcel map. [COA] [PUBLIC WORKS]

BP-34. WATER MAIN RELOCATION PLANS:

Submit improvement plans for the on-site public water main relocation separate from the off-site improvement plans and the Building on-site improvement plans as the water line relocation plans are approved through a Public Works Encroachment Permit process. The water line relocation shown Sheets TM 1 thru TM-5 and off-site improvements Sheets C1.0 thru C8.0 dated 01/14/19 are subject to change during the plan check process.

[SDR] [PUBLIC WORKS]

BP-35. BUILDING PERMIT ISSUANCE:

Prior to building permit issuance, the existing PG&E easement shall be quitclaimed. Provide documentation in support of extinguishment to Department of Public Works.

Prior to building/garage foundation permit issuance, existing water and storm mains traversing parcels are to be abandoned.
[COA] [PLANNING/PUBLIC WORKS]

EP: THE FOLLOWING CONDITIONS SHALL BE ADDRESSED AS PART OF AN ENCROACHMENT PERMIT APPLICATION.

EP-1. PEERY PARK SPECIFIC PLAN:

This project is in the Peery Park Specific Plan (PPSP) area; therefore, the developer shall comply with any applicable design requirements as identified in the PPSP or as amended and approved by the City. [COA] [PUBLIC WORKS]

EP-2. COMPLETE OFF-SITE IMPROVEMENT PLAN SET:

A complete plan check set applicable to the project, including street improvement plans, streetlight plans, streetscape plans, traffic signing and striping plans, traffic control plans, photometrics, erosion control shall be submitted as part of the first off-site improvement plans, including on-site and off-site engineering cost estimate. Joint trench plans may be submitted later. No partial sets are allowed unless otherwise approved by the Department of Public Works.

Submit improvement plans for public water line relocation separate from the off-site improvement plans and the Building on-site improvement plans as the water line relocation plans are approved through a Public Works Encroachment Permit process. Sheets TM 1 thru TM-5 and off-site improvements Sheets C1.0 thru C8.0 dated 01/14/19 are subject to change during plan check process. Pay initial Engineer and Inspection plan review fee with the first off-site improvement plan submittal. See Improvement Plan Checklist and Submittal Checklist both available on City's website:

https://sunnyvale.ca.gov/civicax/filebank/blobdload.aspx?BlobID=24 002

https://sunnyvale.ca.gov/civicax/filebank/blobdload.aspx?BlobID=23 625 [COA] [PUBLIC WORKS]

EP-3. BENCHMARKS:

The off-site improvement plans shall be prepared by using City's latest benchmarks (NAVD88) available on City's website https://sunnyvale.ca.gov/civicax/filebank/blobdload.aspx?BlobID=2 3803 Plans based on NGVD29 will not be accepted. [COA] [PUBLIC WORKS]

EP-4. UPGRADE OF EXISTING PUBLIC IMPROVEMENTS:

As part of the off-site improvement plan review and approval, any existing public improvements to be re-used by the project, which are not in accordance with current City standards and are not specifically identified in the herein project conditions (such as backflow preventers, sign posts, etc.), shall be upgraded to current City standards and as required by the Department of Public Works. [COA] [PUBLIC WORKS]

EP-5. UTILITY CONNECTION:

This project requires connection to all City utilities or private utilities operating under a City or State franchise which provide adequate levels of service. [COA] [PUBLIC WORKS]

EP-6. UTILITY CONNECTION TO THE MAIN:

All sanitary sewer laterals connecting to the existing main line shall be at a new sanitary sewer manhole. All storm drain laterals connecting to the main shall be at a new storm drain manhole, except where a pipe to pipe connection is permitted if the mainline is 36" or larger, or a junction structure is permitted where the point of connection is within close vicinity of an existing down-stream manhole. Pursuant to City design standards, any new and retrofitted manholes require Sewpercoat, Mainstay or Sancon calcium aluminate cementitious mortar coating of the interior. [SDR] [PUBLIC WORKS]

EP-7. POTHOLING OF EXISTING DRY UTILITIES:

Concurrent with the initial submittal of off-site improvement plans, obtain an encroachment permit for potholing purposes to locate

existing dry utilities. Use pothole information to identify possible conflict between the proposed location of City trees and existing utilities, proposed joint trench, and proposed connection of gravity utilities. Potholing is to take place in a timely manner so that this does not hold up the review of the improvement plans. [COA] [PUBLIC WORKS]

EP-8. EXISTING UTILITY ABANDONMENT:

Developer is responsible for research on all existing utility lines to ensure that there are no conflicts with the project. All existing utility lines (public or private) and/or their appurtenances not serving the project and/or have conflicts with the project, shall be capped, abandoned, removed, relocated and/or disposed of to the satisfaction of the City. Existing public facilities within the street right-of-way shall be abandoned per City's Abandonment Notes and procedures, including abandonment by other utility owners. [COA] [PUBLIC WORKS]

EP-9. MODIFICATIONS TO EXISTING PUBLIC UTILITIES:

Developer is required to pay for all changes or modifications to existing city utilities, streets and other public utilities within or adjacent to the project site, including but not limited to utility facilities/conduits/vaults relocation due to grade change in the sidewalk area, caused by the development. [COA] [PUBLIC WORKS]

EP-10. DRY UTILITIES:

Submit dry utility plans and/or joint trench plans (PG&E, telephone, cable TV, fiber optic, etc.) to the Public Works Department for review and approval prior to issuance of any permits for utility work within any public right-of-way or public utility easements. Separate encroachment permits shall be required for various dry utility construction. [SDR] [PUBLIC WORKS]

EP-11. WET UTILITIES:

All wet utilities (water, sanitary sewer, storm drain) on private property shall be privately owned and maintained. The fire and domestic water systems shall be privately owned and maintained beyond the meter. [COA] [PUBLIC WORKS]

EP-12. RE-USE OF EXISTING CITY UTILITY SERVICE LINES:

The re-use of existing City water service lines is not allowed. Re-use of existing City sanitary sewer and storm drain service lines and appurtenances is subject to City's review and approval. Developer's contractor shall expose the existing facilities during construction for City's evaluation or provide video footage of the existing pipe condition. Developer's contractor shall replace any deficient facilities as deemed

necessary by Public Works Department. Sheets TM 1 thru TM-5 and off-site improvements Sheets C1.0 thru C8.0 dated 01/14/19 are subject to change during plan check process. [COA] [PUBLIC WORKS]

EP-13. SEPARATE DOMESTIC/FIRE PROTECTION SERVICE LINE:

Provide separate fire and domestic service lines to each building. Provide separate fire service tap(s) to the street main for any on-site fire hydrants. Install reduced pressure detector assembly (RPDA) behind the street right-of-way for the domestic service line and a double check detector assembly (DCDA) behind the street right-of-way for the fire service line. [COA] [PUBLIC WORKS/PUBLIC SAFETY-FIRE PREVENTION]

EP-14. PUBLIC FIRE HYDRANTS:

Remove and replace the existing fire hydrant barrel(s) along Mathilda Avenue and Sobrante Way with current City standard Clow-Rich 75. New fire hydrant location shall be per current City standard detail 2B and 2B-2. Public fire hydrant shall be maintained free and clear of all trees, vines, shrubs, bushes, ivy, etc. for a minimum of three feet. [COA] [PUBLIC WORKS/PUBLIC SAFETY-FIRE PROTECTION]

EP-15. WATER METER:

Building shall have its own domestic water service connection to the water main with domestic radio-read water meter and reduced pressure backflow prevention devices per current City standards. For water meter sizes three (3) inches or larger, provide meter sizing calculations to Public Works Department for approval of meter size, as part of the off-site improvement plan submittal. If the buildings water demand requires a water meter 3" or larger, installation of dual meters and a cut-in tee are required per City standard detail 12B and 12B-1. Provide separate fire service taps with separate reduced pressure detector assembly in accordance with current City standards. Install new radio-read water meter(s) for each point of connection to the water main. Install new backflow prevention devices on the discharge side of water service line on private property. Install backflow preventer enclosure where applicable. [SDR] [PUBLIC WORKS]

EP-16. IRRIGATION SERVICE LINE AND BACKFLOW PREVENTORS:

Install a separate irrigation water service line (separate from the domestic water service line) with a meter and backflow prevention device.

All landscape and irrigation systems, located in the public park strip areas shall be connected to the water system metered to the property owner. Install new reduced pressure backflow prevention devices on the discharge side of irrigation line on private property. Install backflow

preventer enclosure where applicable. Backflows must adhere to City's Cross-Connection Program. Backflow inspection permit and tags are required for all backflow devices. [COA] [PUBLIC WORKS]

EP-17. SANITARY SEWER AND STORMDRAIN MANHOLES:

Install new sanitary sewer and storm drain manholes at the street rightof-way lines for all existing and proposed sanitary sewer laterals and proposed storm drain laterals to be used for the project. [SDR] [PUBLIC WORKS]

EP-18. SANITARY SEWER VIDEO:

The contractor shall make a video copy of the interior of the new sanitary sewer mainline installed prior to it is put into service. [COA] [PUBLIC WORKS]

EP-19. SANITARY SEWER AND STORM DRAIN TRIBUTARY PATTERN:

This project is required to follow the existing sanitary sewer and storm drain tributary pattern. Any deviations would require additional analysis and be subject to approval by the Department of Public Works as part of the off-site improvement plan review process. This project shall not cause any negative impact on the drainage pattern for adjacent properties. [COA] [PUBLIC WORKS]

EP-20. STORM DRAIN DESIGN

Provide storm drain hydrology and hydraulic calculations based upon a 10-year storm event to justify the size of the storm drain lateral flowing full. The project impact to the existing storm drain main shall retain 1' below the lowest public street gutter flow elevation. The new storm drain main line shall be minimum 15 inches diameter. [COA] [PUBLIC WORKS]

EP-21. CATCH BASIN TRASH CAPTURE DEVICES AND BADGE/STENCILING: Pursuant to SMC 12.60.130, install full trash capture device on the project site, prior to connecting to the City's storm drain collection system. The developer shall be responsible for perpetual maintenance of those trash capture devices. All storm drain inlet facilities located in the public right-of-way shall be stenciled and/or have a badge that reads "NO DUMPING". Stencils/badges may be supplied by the Environmental Services Department if needed. [COA] [PLANNING/ENVIRONMENTAL SERVICES/PUBLIC WORKS]

EP-22. UTILITY METER/VAULT:

No existing or new utility meters or vaults shall be located within the new driveway approach areas. All existing or new utility vaults serving the project site shall be located on-site and not within the public utility easement, if any. [COA] [PUBLIC WORKS]

EP-23. DRIVEWAY APPROACHES:

Remove existing driveway approaches and install new driveway approaches along the project frontage to comply with Americans with Disabilities Act (ADA) requirements and per city standard details and specifications or as approved by Department of Public Works. All unused existing driveway approaches shall be replaced with new curb, gutter and sidewalk. [COA] [PUBLIC WORKS]

EP-24. STREETSCAPE IMPROVEMENTS:

Sobrante Avenue: Remove existing southerly 85' to 90' of existing curb and gutter along project frontage. Install new 2' gutter, 6" curb and 6' wide sidewalk with 5' wide park strip (measured from the back of curb).

Mathilda Avenue: Remove existing curb, gutter and sidewalk along project frontage or as approved by Department of Public Works. Install new 2' gutter, 6" curb and 14' wide sidewalk (measured from the back of curb) with 6'x5' tree wells (spaced approximately 30'-35').

Provide sidewalk transition to conform to existing sidewalks at project limits. Provide street dedication and sidewalk easements as needed. [COA] [PUBLIC WORKS]

EP-25. STREET PAVEMENT:

Sobrante Avenue: Applicant shall coordinate with Santa Clara County on street pavement restoration. Applicant is to submit Santa Clara County documentation stating requirement restoration to the City of Sunnyvale.

Mathilda Avenue: Type III Slurry Seal along project frontage from lip of gutter to lip of gutter on both sides of Mathilda median. Mathilda Avenue is currently on Street Moratorium List as it was slurry sealed in 2016. Moratorium expires 12/2019. Final limit of street restoration is to be coordinated with DPW Inspector and Project Engineer prior to completion of work. [SDR] [PUBLIC WORKS]

EP-26. PHOTOMETRIC ANALYSIS:

The developer shall provide a photometric analysis for project frontages, North Mathilda Avenue and Sobrante Way so as to determine the location of new street lighting to meet the current City's Roadway Lighting Design Criteria. Roadway, Sidewalk, Crosswalk Illuminance calculations shall be calculated separate from each other.

The roadway and sidewalk illuminance values required to be met for North Mathilda Avenue are:

Minimum Maintained Average Illuminance ≥ 1.2 fc

Uniformity Ratio (Avg/Min) ≤ 3.0

Max/Min ratio ≤ 20

The roadway and sidewalk illuminance values required to be met for Sobrante Way are:

Minimum Maintained Average Illuminance ≥ 0.7 fc

Uniformity Ratio (Avg/Min) \leq 6.0

Max/Min ratio ≤ 20

The limits of the photometric analysis shall be for the entire segment required with all streetlights being LED fixtures on both sides of the street. The photometric analysis shall identify where new streetlights would need to be installed for the entire street block.

Developer shall install new streetlights and remove and replace/upgrade conduits, wires, pull boxes, and conductors (to current City standards) along project frontages, North Mathilda Avenue and Sobrante Way based upon City approved photometric analysis, unless otherwise directed by the City. All LED fixtures shall be of the same make and model (current approved manufacturer is Philips Lumec). Street light fixtures shall be per PPSP (Mathilda Avenue shall have PP-1 and PP-2 streetlights and Sobrante Way shall have PP-2 streetlights).

For photometric analysis: LLF factor to be used is 0.95. The LED fixture should have an efficiency of at least 90 lumens/watt and should have the International Dark-Sky Association (IDA) fixture seal of approval (FSA) and be on their IDA-Approved™ Products list. Along with the photometric analysis the developer shall provide cut sheets for proposed fixture, ies files used to perform analysis, test results from certified independent lab, and electronic copy of the photometric analysis in AGi32 format. All LED fixtures shall have a 10-year warranty.

Submit separate streetlight plans concurrently with the off-site improvement plan review to include installation of new conduits, existing and/or new locations of power source connection and new service pedestal, conductors, pull boxes, voltage drop and load calculations, and any other streetlight equipment as required to be

installed by the Developer per latest City standard details and specifications and National Electric Code.

Developer shall comply with City street light design guidelines and plan check submittal requirements as provided by the City upon request.

Obtain PG&E's approval for new service pedestal, if required, prior to Encroachment Permit issuance by Public Works Department.

[COA] [PUBLIC WORKS]

EP-27. SIGNING AND STRIPING PLANS:

Submit a signing and striping plan in accordance with the latest edition of the CA MUTCD to City for Mathilda Avenue review and approval by the Public Works Department as well as Santa Clara County for Sobrante Way review and approval. Newly installed travel and bike lane lines shall be replaced at current locations, or as directed to by the Department of Public Works. [SDR] [PUBLIC WORKS]

EP-28. TRAFFIC CONTROL PLAN:

Submit a traffic control plan with the off-site improvement plans for review and approval. Per the City's Temporary Traffic Control Checklist, the traffic control plan shall include a summary of the traffic control types, dates, times and blocks affected. All construction related materials, equipment, and construction workers parking need to be stored on-site and the public streets need to be kept free and clear of construction debris. [COA] [PUBLIC WORKS]

EP-29. CITY STREET TREES:

The developer shall install required street trees along the project frontage as follows:

Sobrante Avenue: Quercus agrifolia - California Coast Live Oak

Mathilda Avenue: Quercus frainetto - Italian Oak

Street trees and frontage landscaping shall be included in the detailed landscape and irrigation plan subject to review and approval by the Department of Public Works prior to issuance of encroachment permit. New street trees shall be 24-inch box size or 15-gallon size. The city tree spacing should be approximately 35 feet apart. A continuous root barrier shall be installed along the park strip area. No trees are to be planted within 10' of a sanitary sewer lateral. [SDR] [PUBLIC WORKS]

EP-30. PROTECTION OF EXISTING TREES:

No utility trench shall be allowed within 15' radius of an existing mature tree. Boring, air spade or other excavation method as approved

by the City Arborist shall be considered to protect existing mature tree. Consult with the City Arborist prior to adjusting locations of utility lines. [SDR] [PUBLIC WORKS]

EP-31. DAMAGE TO EXISTING PUBLIC IMPROVEMENTS:

Developer shall be responsible to rectify any damage to the existing public improvements fronting and adjacent to the project site because of project construction to City's satisfaction by the Department of Public Works. All existing traffic detector loops and conduits shall be protected in place during construction. Any damaged detector loops shall be replaced within 7 days at the expense of the developer. [COA] [PUBLIC WORKS]

EP-32. VTA COORDINATION:

Developer shall notify VTA of the proposed plans to determine if any VTA improvements are necessary or if any VTA lines will be impacted during construction. Developer shall work with VTA directly on these improvements which may include installation of a covered bus stop with a bench and bus pad, subject to City's concurrence. Applicant to the City written documentation from shall provide acknowledging the project and/or implementing requirements... VTA contact is Robert Daniels, Service & Operations Planning (408) 321-5780. Improvements required by VTA shall be included on the off-site improvement plans. If bus pad is required, service laterals for wet utilities shall not be installed underneath bus pad. [COA] [PUBLIC WORKS]

EP-33. SANTA CLARA COUNTY COORDINATION:

This project requires the approval/permit from Santa Clara County for construction next to or within their right-of-way. Approval from Santa Clara County shall be provided to City of Sunnyvale.

Applicant shall coordinate with Santa Clara County in the preparation of plat and legal for the conveyance of County owned 20' wide sliver of right-of-way along Mathilda Avenue to the City of Sunnyvale. Plat and legal is to be reviewed and approved by Santa Clara County in concurrence with City of Sunnyvale.

Mathilda Avenue: Santa Clara County maintains a 20' wide sliver of project frontage adjacent to City of Sunnyvale right-of-way (ROW). Applicant shall coordinate with Santa Clara County for the construction of new sidewalk and maintenance agreement as required by Santa Clara County. Provide a copy of the agreement to Department of Public Works.

Sobrante Way: Sobrante Way is maintained by Santa Clara County. Applicant shall coordinate with Santa Clara County for easement and maintenance agreement as required by Santa Clara County. Provide documentation to Department of Public Works. Sobrante Way may require 1' easement conveyed to Santa Clara County in order to install the required streetscape. Applicant shall coordinate with Santa Clara County as required. Provide a copy of the agreement and recorded document to Department of Public Works. [COA] [PUBLIC WORKS]

EP-34. RECORD DRAWINGS:

Stamped and signed hard copy record drawings of the off-site improvements (including off-site street, sewer, water, storm drain and landscaping plans) shall be submitted to the City prior to encroachment permit sign-off. In addition, streetlight record drawings shall be in AutoCAD format. Developer shall pay the record drawing fee. [COA] [PUBLIC WORKS]

EP-35. PUBLIC WORKS DEVELOPMENT FEES:

Developer shall pay all applicable Public Works development fees associated with the project, including but not limited to, utility frontage and/or connection fees, off-site improvement plan check and inspection fees, prior to map recordation or any permit issuance, whichever occurs first. The exact fee amount shall be determined based upon the fiscal year fee schedule rate at the time of fee payment. [COA] [PUBLIC WORKS]

PM: THE FOLLOWING CONDITIONS SHALL BE MET PRIOR TO THE APPROVAL OF THE FINAL MAP OR PARCEL MAP.

PM-1. PARCEL MAP COMPLIANCE WITH TENTATIVE PARCEL MAP:

The parcel map shall be substantially the same as the tentative parcel map. Any alteration of the tentative parcel map after the tentative parcel map is approved is subject to additional approval by the City and may require a public hearing. Sheet TM1 thru TM5 of Tentative Parcel Map submittal dated 01/14/19 is subject to change during plan check process. [COA] [PUBLIC WORKS]

PM-2. TITLE 18 AND SUBDIVISION MAP ACT:

The submittal, approval and recordation of the parcel map for lot merger purposes shall be in accordance with the provisions of the California Subdivision Map Act and Sunnyvale Municipal Code Title 18 subdivision requirements. [COA] [PUBLIC WORKS]

PM-3. EASEMENT DEDICATION:

New sidewalk easement of 7' on Mathilda Avenue shall be delineated on the map. Easement shall be kept open and free from buildings and structures of any kind except those appurtenances associated with the defined easement. [COA] [PUBLIC WORKS]

PM-4. WATER EASEMENT DEDICATION:

Public water easements shall be dedicated for the installation of a 12" PVC water main and domestic and irrigation laterals on the southerly side of the parcel per Department of Public Works guidelines. Easement shall be kept open and free from buildings and structures of any kind except those appurtenances associated with the defined easement. [COA] [PUBLIC WORKS]

PM-5. EMERGENCY VEHICLE ACCESS EASEMENT:

Developer shall dedicate a minimum 26'-wide emergency vehicle ingress-egress easement over the surface parking areas, excepting areas for parking stalls along the south side of the parcel. [COA][PUBLIC SAFETY/PUBLIC WORKS]

PM-6. ABANDONMENT OF PUBLIC EASEMENTS:

Existing landscape easement along the Mathilda Avenue frontage is to be abandoned. [COA][PUBLIC WORKS]

PM-7. RESERVATION/ABANDONMENT OF EASEMENTS:

Reservation of new and/or abandonment of existing public/private utility easement(s), ingress/egress easement(s) necessary for the project site shall be delineated on the map or recorded concurrently with the map with a separate instrument, unless otherwise approved by the Department of Public Works. Quitclaim deed is required for abandonment of private easements prior to map recordation. All easements shall be kept open and free from buildings and structures of any kind except those appurtenances associated with the defined easements. [COA] [PUBLIC WORKS]

PM-8. UTILITY COMPANY APPROVAL:

Obtain approval letters from various utility companies for the parcel map in regards to any existing or new easements associated with the project. [COA] [PUBLIC WORKS]

PM-9. SUBDIVISION IMPROVEMENT AGREEMENT AND SECURITIES:

Developer shall execute a Subdivision Agreement and provide improvement securities and/or cash deposit(s) for all proposed public improvements prior to parcel map recordation or any permit issuance, whichever occurs first. [COA] [PUBLIC WORKS]

PM-10. OFF-SITE IMPROVEMENT COST ESTIMATE:

Provide an itemized engineer's estimate for all off-site public improvements for the entire project. [COA] [PUBLIC WORKS]

PF: THE FOLLOWING CONDITIONS SHALL BE ADDRESSED ON THE CONSTRUCTION PLANS AND/OR SHALL BE MET PRIOR TO RELEASE OF UTILITIES OR ISSUANCE OF A CERTIFICATE OF OCCUPANCY.

PF-1. LANDSCAPING AND IRRIGATION:

All landscaping and irrigation as contained in the approved building permit plan shall be installed prior to occupancy. [COA] [PLANNING]

PF-2. PARKING LOT STRIPING:

All parking lot striping, carpool and compact spaces shall be striped as per the approved plans and Public Works standards. [COA] (PLANNING/ENGINEERING)

any change in officers and provide the names, addresses and telephone numbers of the new officers within thirty (30) days after the change becomes effective. [COA] [PLANNING]

PF-3. IRRIGATION METERS:

For commercial and industrial projects, to ensure appropriate sewer billing (water used for irrigation may not be billed for sewer), the developer may provide separate (irrigation and other) intake meters. Such meters could be installed prior to occupancy of the building. [COA] [PLANNING]

PF-4. COMPLETION OF PUBLIC IMPROVEMENTS:

Developer shall complete all required public improvements in accordance with City approved plans, prior to any building occupancy. [COA] [PUBLIC WORKS]

DC: THE FOLLOWING CONDITIONS SHALL BE COMPLIED WITH AT ALL TIMES DURING THE CONSTRUCTION PHASE OF THE PROJECT.

DC-1. BLUEPRINT FOR A CLEAN BAY:

The project shall be in compliance with stormwater best management practices for general construction activity until the project is completed and either final occupancy has been granted. [SDR] [PLANNING]

DC-2. TREE PROTECTION:

All tree protection shall be maintained, as indicated in the tree protection plan, until construction has been completed and the installation of landscaping has begun. [COA] [PLANNING]

DC-3. CLIMATE ACTION PLAN – OFF ROAD EQUIPMENT REQUIREMENT:

- OR 2.1: Idling times will be minimized either by shutting equipment off when not in use or reducing the maximum idling time to 5 minutes (as required by the California airborne toxics control measure Title 13, Section 2485 of California Code of Regulations [CCR]), or less. Clear signage will be provided at all access points to remind construction workers of idling restrictions.
- OR 2.2: Construction equipment must be maintained per manufacturer's specifications.
- OR 2.3: Planning and Building staff will work with project applicants to limit GHG emissions from construction equipment by selecting one of the following measures, at a minimum, as appropriate to the construction project:
 - a) Substitute electrified or hybrid equipment for diesel- and gasoline-powered equipment where practical.
 - b) Use alternatively fueled construction equipment on-site, where feasible, such as compressed natural gas (CNG), liquefied natural gas (LNG), propane, or biodiesel.
 - c) Avoid the use of on-site generators by connecting to grid electricity or utilizing solar-powered equipment.
 - d) Limit heavy-duty equipment idling time to a period of 3 minutes or less, exceeding CARB regulation minimum requirements of 5 minutes. [COA] [PLANNING]

DC-4. DUST CONTROL:

At all times, the Bay Area Air Quality Management District's CEQA Guidelines and "Basic Construction Mitigation Measures Recommended for All Proposed Projects", shall be implemented. [COA] [PLANNING]

AT: THE FOLLOWING CONDITIONS SHALL BE COMPLIED WITH AT ALL TIMES THAT THE USE PERMITTED BY THIS PLANNING APPLICATION OCCUPIES THE PREMISES.

AT-1. DELIVERY HOURS:

Delivery hours for the approved use shall comply with SMC 19.42.030:

- a) Delivery hours are limited to daytime (period from 7:00 a.m. to 10:00 p.m. daily) only.
- b) Nighttime delivery (period from 10 p.m. to 7:00 a.m. daily) is prohibited. [SDR] [PLANNING]

AT-2. RECYCLING AND SOLID WASTE:

All exterior recycling and solid waste shall be confined to approved receptacles and enclosures. [COA] [PLANNING]

AT-3. EXTERIOR EQUIPMENT:

All unenclosed materials, equipment and/or supplies of any kind shall be maintained within approved enclosure area. Any stacked or stored items shall not exceed the height of the enclosure. Individual air conditioning units shall be screened with architecture or landscaping features. [COA] [PLANNING]

AT-4. LANDSCAPE MAINTENANCE:

All landscaping shall be installed in accordance with the approved landscape plan and shall thereafter be maintained in a neat, clean, and healthful condition. Trees shall be allowed to grow to the full genetic height and habit (trees shall not be topped). Trees shall be maintained using standard arboriculture practices. [COA] [PLANNING]

AT-5. PARKING MANAGEMENT:

On-Site parking management shall conform with the approved parking management plan. [COA] [PLANNING]

AT-6. PARKING LOT MAINTENANCE:

The parking lot shall be maintained in accordance with the approved plans and as follows:

- a) Clearly mark all employee, customer, and compact spaces. This shall be specified on the Building Permit plans and completed prior to occupancy.
- b) Maintain all parking lot striping and marking.
- c) Assure that adequate lighting is available in parking lots to keep them safe and desirable for the use.
- d) Require signs to direct vehicles to additional parking spaces onsite, as needed.
- e) Clearly mark all compact spaces as per approved plans. [COA] [PLANNING]
- b) Clearly mark all assigned, guest, and compact spaces. This shall be specified on the Building Permit plans and completed prior to occupancy.
- c) Maintain all parking lot striping and marking.

d) Maintain parking lot lighting and exterior lighting to ensure that the parking lot is maintained in a safe and desirable manner for residents and/or patrons. [COA] [PLANNING]

AT-7. BMP MAINTENANCE:

The project applicant, owner, landlord, or HOA, must properly maintain any structural or treatment control best management practices to be implemented in the project, as described in the approved Stormwater Management Plan and indicated on the approved building permit plans. [SDR] [PLANNING]

AT-8. BMP RIGHT OF ENTRY:

The project applicant, owner, landlord, or HOA, shall provide access to the extent allowable by law for representatives of city, the local vector control district, and the Regional Water Quality Control Board, strictly for the purposes of verification of proper operation and maintenance for the storm water treatment best management practices contained in the approved Storm Water Management Plan.[SDR] [PLANNING]

AT-9. TENANT LEASE AGREEMENTS:

Any new lease agreements shall include the following provisions:

- a) Tenants shall be notified of their responsibility and shall agree to implement and manage the approved Transportation Demand Management Program.
- b) Tenants shall be notified of their responsibility and shall agree to construct all tenant improvements to meet a minimum of LEED Gold standard (with efforts to achieve LEED Platinum standards) and maintain facilities consistent with LEED Gold standards (or LEED Platinum if feasible) and USGBC certification. [COA] [PLANNING]